

Rasdhoo Stack Foundation

Scope of Works

The scope of this project is to lay the foundation for exhaust stacks for Aa. Rasdhoo new powerhouse:

- Demolition and Dismantling:
The contractor is expected to dismantle and demolish any existing structures at the site including the disposal of all the items unless otherwise stated by STELCO.
- Site clearance and Excavation:
The contractor is expected to clear the site of any vegetation and debris and make sure the site is level and in good condition to lay the foundation. The contractor is expected to carry out all the earth works including excavation and backfilling up to the required level.
- Foundation and Concrete works:
The contractor is expected to do all the concrete work including the formwork and reinforcement. All finishing works are included in the contractor's scope of works.
All the materials used should be submitted to STELCO beforehand and approved for use.